

# NEWCASTLE, ROCKLIN, GOLD HILL CEMETERY DISTRICT

## TRUSTEES

Mark Riemer  
Rocklin, CA 95677

Grant Kageta  
Loomis, CA 95650

Roy Hebard Jr.  
Loomis, CA 95650

850 TAYLOR ROAD  
NEWCASTLE, CA 95658  
(916) 663-4660  
FAX (916) 663-4313

## TRUSTEES

Gordon Takemoto  
Loomis, CA 95650

Jenny Knisley  
Loomis, CA 95650

Jeff Forrey  
District Manager

Date: 06/12/2026

To: ALL PLAN HOLDERS

## RE: Addendum No. 2

This Addendum is applicable to work designated herein and shall be a part of and be included in the Contract Documents for:

**Project: Rocklin Cemetery Pavement Project**  
**Job#: 2026.2**

This Addendum consists of:

General Project Questions and Plans and Specification Changes

Acknowledge receipt of this Addendum in the space provided on the Proposal/Bid form.

### 1. GENERAL QUESTIONS:

- a. *Bid Items #2 & #3 call out for 3/6 and 3/3 respectively. Details 1 & 2 call for the same except where it specifies "3 inches 1/2 minus asphalt concrete." Below that it states "3 & 6" inches. Please clarify if we are to price 3" of AC or 3 1/2" ac over the 6" AB section.*
  - i. **Where noted at locations on the plans, it shall be 3 inches of AC over 6 inches of AB. See update plan sheet C1 for new legend and notes.**
  
- b. *Bid Item #9 lists 1 LF on the base bid schedule however, on the plans the quantity is measured as ~40 LF on the plans. Please confirm.*
  - i. **See updated bid sheet.**
  
- c. *Will traffic flow plans or traffic control plans be required?*
  - i. **See updated sheet C1, general notes.**

d. *Will grinding spoils be disposed offsite or onsite?*

i. **See updated sheet C1, general notes.**

e. *What are the requirements for piping inside the existing two vaults.*

i. **See updated sheet C2, detail 9 notes.**

f. *How long can water be shut off for all connections within the two vaults?*

i. **See updated sheet C2, detail 9 notes.**

g. *Will water be supplied for the project?*

i. **See updated sheet C1, general notes.**

h. *Are there any known existing utilities not marked on the plans within the roadway?*

i. **See updated sheet C1.**

i. *Who is responsible for removing the existing two concrete vaults?*

i. **The contractor. See sheet C1, R4 note.**

j. *Does the existing AC berm on some of the existing roadway sections need to be removed and replaced?*

i. **The existing AC berm shall be removed as part of the grinding process. The AC berm is NOT to be reinstalled.**

k. *Can we shut the cemetery down for the project?*

i. **See updated sheet C1, general notes.**

l. *It appears base bid item 7 includes base bid item 12. Please clarify.*

i. **Removed base bid item 12 from the bid sheet. See updated bid sheet.**

*m. CLARIFICATION OF BID EVALUATION AND AWARD OF CONTRACT*

- i. The intent of the Bid Form is that all bidders shall submit pricing for the Base Bid, Bid Deductive Alternate No. 1, and Bid Deductive Alternate No. 2.**
- ii. For purposes of bid evaluation and determination of the apparent low bidder, the Total Bid Price shall be calculated as follows:
  - 1. TOTAL BID PRICE = BASE BID + BID DEDUCTIVE ALTERNATE NO. 1 + BID DEDUCTIVE ALTERNATE NO. 2****
- iii. The Contract shall be awarded to the lowest responsive and responsible bidder based on the Total Bid Price as defined above.**
- iv. Following determination of the lowest responsive and responsible bidder, the District reserves the right, at its sole discretion and based upon available project funding, to award the Contract for the full scope of work or to deduct Bid Deductive Alternate No. 1, Bid Deductive Alternate No. 2, or both Bid Deductive Alternates from the awarded Contract amount.**
- v. The District's decision regarding inclusion or exclusion of the deductive alternates shall not affect the determination of the lowest responsive and responsible bidder, which shall be based solely upon the Total Bid Price submitted on the Bid Form.**

**END OF ADDENDUM**